

Table 3: Resource Summary by Rock-type and Cut-off Grade

RockCode	Cutoff Grade Fe%	Tonnes '000	Fe%	SiO2%	P%	Al2O3%
<i>Siliceous Ironstone</i>						
20	50	213	56.96	16.41	0.01	0.75
20	45	1,006	48.49	27.97	0.01	1.31
20	40	1,576	46.97	30.13	0.01	1.33
20	35	1,924	45.08	32.63	0.01	1.5
20	30	4,595	37.92	42.92	0.02	1.54
20	25	6,613	34.63	47.64	0.02	1.66
20	20	9,215	31.26	52.87	0.02	1.41
20	15	11,894	28.14	57.54	0.02	1.24
20	10	13,276	26.56	59.74	0.02	1.25
20	5	13,328	26.49	59.84	0.02	1.25
20	TOTAL	16,945	20.83	47.06	0.02	1.13
<i>Haematitic Ironstone</i>						
30	50	4,874	55.22	20.52	0.01	0.49
30	45	8,689	52.03	24.70	0.01	0.55
30	40	10,036	50.80	26.14	0.01	0.68
30	35	11,074	49.56	27.49	0.02	0.81
30	30	11,581	48.81	28.16	0.02	0.92
30	25	11,749	48.51	28.41	0.02	0.93
30	20	11,928	48.12	28.72	0.02	0.94
30	15	11,997	47.95	28.85	0.02	0.94
30	10	12,110	47.63	29.08	0.02	0.94
30	5	12,110	47.63	29.08	0.02	0.94
30	TOTAL	13,839	41.68	25.45	0.02	0.82

RockCode	Cutoff Grade Fe%	Tonnes '000	Fe%	SiO2%	P%	Al2O3%
<i>Total Ironstone</i>						
ALL	50	5,087	55.29	20.34	0.01	0.5
ALL	45	9,696	51.66	25.04	0.01	0.63
ALL	40	11,611	50.28	26.68	0.01	0.77
ALL	35	12,998	48.90	28.25	0.01	0.91
ALL	30	16,176	45.72	32.35	0.02	1.1
ALL	25	18,361	43.51	35.34	0.02	1.19
ALL	20	21,142	40.77	39.24	0.02	1.15
ALL	15	23,891	38.09	43.13	0.02	1.09
ALL	10	25,386	36.61	45.12	0.02	1.1
ALL	5	25,437	36.55	45.20	0.02	1.1
ALL	TOTAL	30,784	30.20	37.35	0.02	0.99